

1 **CHALLENGES TO DELIVERING CHANGE OVERNIGHT: BUS REFORM IN**
2 **ULAANBAATAR**

3

4 **Jean Paul Velez**

5 The World Bank

6 1818 H St NW, Washington, DC 20433

7 Tel: 202 473-5550 Email: jvelez@worldbank.org

8

9 **Yang Chen**

10 The World Bank

11 1818 H St NW, Washington, DC 20433

12 Tel: 202 458-8618 Email: ychen3@worldbank.org

13

14 **Khaliun Bat Orig**

15 The World Bank

16 1818 H St NW, Washington, DC 20433

17 Email: kbatorig@worldbank.org

18

19 **Arturo Ardila Gomez**

20 The World Bank

21 1818 H St NW, Washington, DC 20433

22 Tel: 202 473-5861 Email: aardilagomez@worldbank.org

23

24 Word count: 6,844 words text + 2 tables/figures x 250 words (each) = 7,344 words

25

26 Submitted on August 1, 2016

27 **ABSTRACT**

28 This paper discusses the challenges to efficient public transport service provision in Ulaanbaatar,
29 Mongolia, and the planning and implementation of the recent ‘Smart Bus’ reforms, to reflect on current
30 public transport reform practices in cities in developing economies. Faced with deteriorating transport
31 conditions, and lacking resources to move forward with desired mass public transport infrastructure
32 investments, Ulaanbaatar opted to use the introduction of new technologies and regulatory reforms to
33 catalyze improvements in service quality, financial management, and broader sector management. Based
34 on two years of research and technical assistance efforts carried out by the World Bank in Ulaanbaatar,
35 the general context of transport in Ulaanbaatar, the motivations and ultimate design of the reforms, and
36 their early outcomes are presented.

37
38 *Keywords: Developing countries, public transport reforms, concessions, ITS.*

39 INTRODUCTION

40 Ulaanbaatar, the capital of Mongolia, is home to 1.4 million people, accounting for 47% of the total
 41 national population (1). It is the national epicenter for government, industrial, financial, and cultural
 42 activities. From 2010 to 2014, Mongolia enjoyed a significant mining boom, leading to an annual average
 43 GDP growth rate of 11.1% (2). During this period Ulaanbaatar became a prominent international hub for
 44 investors, and the banking and construction sectors thrived. Migration from rural areas to the capital city
 45 saw an important increase during those years. More people and more activities led in turn to an important
 46 increase in transport demand in the city, which in 2014 amounted to 3.4 million trips per day (3).
 47 However, transport infrastructure and services in Ulaanbaatar were limited, and most citizens endured
 48 long commute times, congestion, and transport-induced air quality problems.

49 In recent years, both the National Government of Mongolia (NGM) and the Municipal
 50 Government of Ulaanbaatar (MGUB) had explored various infrastructure projects to improve transport
 51 conditions in the city, most notably plans of building a metro system and a BRT system. However, by the
 52 fall of 2014, economic growth had slowed down considerably, and neither project had taken off the
 53 ground; meanwhile, transport conditions in the city continued to deteriorate, and citizens' complaints
 54 were growing louder. As a result, the MGUB decided to implement a series of reforms to improve the
 55 quality of bus services in the city. These reforms combined the introduction of an integrated fare
 56 collection system and other intelligent transport systems (ITS) tools, with strategic regulatory reforms, to
 57 catalyze improvements in service quality, financial management, and broader sector management. The
 58 reforms were put in place in July 2015; six months later, in December 2105, the reforms had failed to
 59 deliver any of the desired outcomes.

60 This paper illustrates the case of Ulaanbaatar and the 'Smart Bus' reforms to reflect on the
 61 challenges faced by many cities in developing economies where public resources are limited, but the
 62 needs to improve transport conditions are pressing. Changes in regulations and other 'soft' measures
 63 might be a tempting alternative to deliver improvements at a limited cost; however, just as in the case of
 64 'hard' infrastructure projects, soft initiatives cannot be improvised and ought to be supported by
 65 comprehensive planning processes. In Ulaanbaatar, as in many other cities in developing economies,
 66 political expediency drove the planning and implementation of the reforms, often disregarding known
 67 sector best practices.

68 Following this Introduction, the paper offers sections on the general transport conditions in
 69 Ulaanbaatar, and a closer look at the public transport system, to then discuss the planning and ongoing
 70 implementation of the Smart Bus reforms, and finally concluding remarks reflecting on the observed
 71 outcomes.

72

73 URBAN TRANSPORT IN ULAANBAATAR

74

75 The city and its transport infrastructure

76 Ulaanbaatar had been developed in low urban density patterns, averaging only 3,419 people per square
 77 kilometer (4). In the central areas of the city, urban forms seemed to derive from Mongolia's soviet-style
 78 legacy of city planning. Large-size blocks served as the structural element, buildings showed limited
 79 heights (4-5 stories on average, 10-12 stories for the highest buildings), and generous open space
 80 allocations were distributed widely in the form of frontages or inner-block courtyards. In the more
 81 peripheral areas of the city, the observed pattern was a patchwork of plots divided by fences, and
 82 occupied with detached single-unit homes ranging from traditional gers (or yurt, a portable, round tent
 83 covered with skins or felt used as a dwelling by nomads in the steppes of Central Asia) to more
 84 permanently built structures. Low-income citizens populated many of these areas, living in gers (thus the
 85 name 'ger area', used as proxy for low-income neighborhood) and lacking basic infrastructure and
 86 services (paved streets, sidewalks, parks, streetlights, water and sanitation, schools, and hospitals).

87 From a land-use perspective, at a city wide level, Ulaanbaatar showcased a highly segregated
 88 monocentric structure. The city's central business district (CBD), located at the very core of the central
 89 area, agglomerated the large majority of government agencies, businesses, trade and services


90 organizations, cultural institutions and universities. The city did not have any other significant activity
91 centers in other areas of the city. As such, on a regular workday, in the morning most people traveled to
92 the CBD, and in the afternoon most people headed back to their homes from the CBD – this dynamic
93 placed an immense amount of pressure on that very confined area of the city and the transport
94 infrastructure that served it. At the neighborhood scale, land use segregation was also widespread.
95 Neighborhoods in the soviet-style central area featured a clear functional division of land-uses, with
96 government, office, commerce, and residential uses distributed in isolated block sets, and with very
97 restricted mixed-use areas. The ger areas were in their vast majority residential areas, and were poorly
98 equipped with services or activities. In fact, people living in the gers often had to travel to the central area
99 to go to work, school, see a doctor, or conduct other basic activities.

100 The road network was the city's the main transport infrastructure; however, the road network
101 showcased an unbalanced road hierarchy and was poorly maintained. The road network consisted of 630
102 km in total, including 132 km of primary roads (21%), 140 km of secondary roads (22%), and 358 km of
103 local access roads (57%) (5). These figures revealed that, compared to best practices, Ulaanbaatar's road
104 network lacked secondary roads providing inter-district connectivity. The city's two distinct urban form
105 patterns also had an impact on the road network. In the central area, there was a structured network of
106 paved streets, marked by a clear grid with a noticeable hierarchy. However, the road density was limited
107 by the central area's large block pattern, with very few roads serving inter-district, while dead end tertiary
108 roads only provided access into the blocks but added very little connectivity. In the ger areas road quality
109 was very poor, as only 10% of streets were paved, and the landscape consisted of steep hills and other
110 complex terrains (6). Moreover, very few roads reached out to the rapidly growing edges of the city, and
111 secondary roads were almost inexistent – instead, for broad stretches of land, the street network was
112 simply a haphazard patchwork of unpaved tertiary roads and makeshift paths.

114 **The local transport experience**


115 In 2014, the average commute time in Ulaanbaatar was approximately 37 minutes, which was relatively
116 long under most comparative measures. A review of average commute times of peer cities in East Asia
117 showed that Ulaanbaatar's average commute took longer than most cities in the sample, and was only
118 surpassed by the average commute times of cities like Bangkok, Manila, or Beijing (see FIGURE 13. Peer
119 city analysis: On top, average commute time vs. population; below, average commute time vs. built-up
120 urban area (7)). Ulaanbaatar's average commute was also comparatively longer than expected given the
121 size of its population or its built-up urban area to the extent that it exceeded the average commute of cities
122 like Seoul or Jakarta, with 17 or 25 times the population of Ulaanbaatar, and 4 or 6 times its built-up
123 urban area.

124



125

126



127

128

129

130

131

132

133


134

FIGURE 1. Peer city analysis: On top, average commute time vs. population; below, average commute time vs. built-up urban area (7).

The modal distribution of commute trips, from highest to lowest share, was: public transport 34%, walking 31%, private cars 23%, taxis 9%, and others 3% (3). Public transport and walking seemed to be favored due to their affordability – public transport fares were relatively cheap (MGT 500, US\$ 0.25), and walking logically had no fare at all. However, neither public transport nor walking allowed for

135 efficient traveling about the city. In the case of public transport, just getting to a bus stop in the vast ger
 136 areas often required long cumbersome walks; typically people were forced to transfer at least once from
 137 one bus route to another to reach their destinations; and buses were often delayed in congested roads in
 138 the central city. In the case of walking, the city's low density and segregated land uses meant that origins
 139 are destinations were simply too far apart for walking to be efficient, particularly so in Mongolia's cold
 140 weather; in the gers, terrains were difficult to manage, and roads lack any provisions for pedestrians; and
 141 in the central area, the large block structure forced long and cumbersome walking paths, while its limited
 142 pedestrian facilities were often overtaken by parked cars.

143 Meanwhile, boosted by years of rapid economic growth, the vehicle fleet in Ulaanbaatar had
 144 doubled from 2004 to 2014, reaching 378 vehicles per 1,000 people (3). Compared to peer cities in East
 145 Asia, Ulaanbaatar's motorization level was only surpassed by cities where motorbikes were the prominent
 146 form of transport such as Jakarta, Hanoi, or Ho Chi Minh City (see FIGURE 24). A more striking notion
 147 was the fact that Ulaanbaatar's motorization level exceeded that of cities like Beijing, Bangkok, Shanghai
 148 or Singapore, which enjoyed considerably higher levels of GDP per capita.
 149



150
 151 **FIGURE 2. Peer city analysis: Motorization levels (7).**
 152

153 Private cars have been allowed to take over most of the city's road space and sidewalks without
 154 much regard for their impact on other mode's efficiency. City officials estimated that while public
 155 transport vehicles only represented 1% of the city's entire vehicle fleet, they serviced 65% of the city's
 156 motorized trips. However, private cars occupied the large majority of the city's streets, and left public
 157 transport vehicles a disproportionately small amount of space given the number of people that they moved,
 158 often becoming the main obstacle to efficient public transport operations. A similar phenomenon took
 159 place on many sidewalks and frontages in the central area, which were commonly invaded by parked
 160 vehicles, making walking troublesome, and often forcing pedestrians to walk on the streets and expose
 161 themselves to vehicle traffic.

162 163 **PUBLIC TRANSPORT**

164 165 **General System Structure**

166 Ulaanbaatar's public transport system consisted primarily of buses, trolleybuses, and microbuses. A total
 167 of 1,155 buses and trolleybuses serviced 79 core routes along the city's main corridors and highest
 168 demand areas (8). In turn, 386 microbuses serviced 49 complementary sub routes of lower demand. These
 169 different routes and services were integrated with one another at the different bus stops distributed
 170 throughout the city. There was a flat fare of MNT 500 (US\$ 0.27) charged to adults for most services, and
 171 a fare of MNT 200 (US\$ 0.11) for children. Students, people with disabilities, law enforcement personnel,
 172 and the elderly, amounting to approximately 40% of the ridership, paid no fare, as they were fully
 173 subsidized by the NGM (8).

174 The public transport system as a whole was regulated by the Transport Department of the Capital
 175 City (TDCC), whose responsibilities included the licensing of bus operating companies, the planning and
 176 awarding of routes, the supervision of operations, and the establishment and revision of fares, among
 177 others. There were 21 different licensed companies providing public transport services. The three largest
 178 companies, controlling the majority of the market, were Bus 1 (the state-owned company), ErdenTrans,
 179 and Tenuunogoo. Under the existing regulatory framework, each company was expected to operate
 180 strictly on the routes and schedules assigned to them by TDCC. However, granted that there was
 181 significant overlap between many routes in high demand areas of the central city, TDCC had established a
 182 monthly passenger quota system to protect the financial viability of all companies and prevent any type of
 183 harmful competition. Each company's quota was assigned on the basis of the different routes that the
 184 company operated, and TDCC's projection of their monthly based on historical data. To enforce company
 185 quotas, TDCC gave a corresponding number of physical tickets to each company, which the companies
 186 have to each passenger when they paid for their fare – if the company ran out of tickets for any given
 187 month, it was expected to stop operating until the start of the following month.

188

189 **Public Transport Service**

190 The outcomes, however, were far from ideal. For starters, the city's sprawling growth pattern and
 191 segregated land uses posed an important challenge to the provision of high quality public transport. The
 192 ger areas, which were mostly residential areas, stretched out through vast swaths of land far away from
 193 the main activity centers in the central city. Running bus routes all the way out to the different gers was
 194 indeed very costly, and much more so at headways associated with high quality services. The city's low
 195 density also meant that public transport riders were scattered and difficult to gather in an efficient manner,
 196 making potential bus fare revenues complicated to amass or insufficient to justify operations.

197 These elements transpired into a far from profitable proposition for any bus company, and, thus,
 198 bus service quality was lacking. Many inhabited areas in the far peripheries of the city were simply not
 199 covered by public transport services. Meanwhile, ger areas closer to the central city were only covered by
 200 a few scattered routes (meaning that local residents had to travel long distances just to get to a bus stop)
 201 and providing infrequent services (meaning that people had fewer opportunities to make desired trips, and
 202 had to wait long times on average to catch a bus). The situation was worsened by the lack of information
 203 about bus routes and schedules at bus stops out in the ger areas, which in effect lead to even longer wait
 204 times and overall low service quality due to unreliability.

205 In the main corridors of the central area, and particularly near the CBD, the elements affecting the
 206 quality of public transport service were different. As detailed earlier, the large block structure and lack of
 207 secondary roads forced most traffic onto very few roads, and given Ulaanbaatar's high number of private
 208 cars, congestion mounted up quickly. The absence of facilities providing priority to public transport
 209 further complicated the situation. Due to their size, buses were less nimble than cars navigating in and out
 210 of traffic flows on congested roads. As such, coming out of bus stops (typically located in a bus bay)
 211 buses were forced to spend additional time waiting and maneuvering back into the main flow, increasing
 212 significantly the effective dwell time of the stop. Compiled over the length of the any route, longer dwell
 213 times amounted to longer travel times for public transport users, and less productive and costlier services
 214 for the operators.

215 However, part of the congestion and delays faced by buses in the central city were created by the
 216 bus system setup itself. Over the years, the city's monocentric structure and segregated land uses had

217 given way to a radial bus route network, structured to provide access from different peripheral areas of the
 218 city to the CBD. As such, given the limited number of roads servicing inter-district traffic flows, many
 219 bus routes overlapped with one another on key roads in the central area. For instance, 26 different bus
 220 routes (serviced by a total of 350 buses) came together and ran next to one another for very long stretches
 221 along Peace Avenue (8). Similarly, 19 different routes (serviced by a total of 220 buses) overlapped along
 222 Chinggis Avenue.

223 Route overlapping surely added congestion to what were already very congested roads, making
 224 bus speeds even slower and travel times longer. It also meant that for lengthy sections of each route buses
 225 would be competing for ridership for buses from other routes. The quota system had been put in place
 226 precisely to mitigate any harmful type of competition by ensuring an equitable split of the revenues.
 227 However, TDCC had very limited resources at its disposal to ensure that bus companies abided by the
 228 quota system. There was no clear system of fines or penalties associated with allowing passengers in a
 229 bus without an official ticket, or for running buses altogether once the company's ticket quota has been
 230 exhausted.

231 The bus system's radial structure also forced people to transfer at least once for trips with origins
 232 and destinations not located near the CBD. Such trips were unnecessarily longer due to their inefficient
 233 route, the prevalent congestion in the central areas, and the time required to transfer. Furthermore, there
 234 was no transfer discount policy in effect, so every transfer required paying one additional full-fare – i.e.,
 235 each transfer doubled the monetary cost of the trip. TDCC estimated that at least 30% of public transport
 236 users needed to make one route transfer to complete their trips – other sources indicated that that figure
 237 could probably be higher (8). This higher cost, product of the route and fare structure, was surely placing
 238 an unfair burden onto many citizens, and could had been deterring countless people from travelling
 239 altogether.

240

241 **The bus company perspective**

242 Bus companies were in a dire financial situation, and reported total industry losses of MNT 17
 243 billion (US\$ 9 million) per year. At the root of this situation was the piecemeal approach by which bus
 244 routes had been planned and allocated to different companies over the years. As a result, the system
 245 functioned in a very fragmented fashion and wasted away potential synergies. Revenues from high
 246 demand corridors were split between too many companies, and there was no mechanism in place to
 247 leverage those funds in support of lower demand routes in the periphery of the city.

248 To compensate, bus companies opted to cut some corners to protect their bottom line. For
 249 instance, instead of paying their drivers and fare collectors a formal salary, bus companies allowed the
 250 driver-collectors tandem to keep all daily revenues minus a daily 'rent' to be paid to the company. If
 251 revenues were higher than the rent, the tandem got to keep the difference; if the revenues were lower than
 252 the rent, the tandem had to pay the company the difference out of their own pocket. This approach
 253 transferred all the demand risk to the driver-collector tandem, incentivizing their focus on revenues rather
 254 than quality of service provision. The consequences of this set up to public transport users and citizens in
 255 general were palpable. Buses often disregarded their routes and schedules to make up additional revenues
 256 in high demand corridors and hours of the day. As such, on top of the 'legal' overlapping of bus routes in
 257 high demand corridors, it was common to find additional buses operating those routes 'illegally' and
 258 competing for passengers with the corridor's assigned services. Meanwhile, low demand routes and
 259 schedules were not even properly fulfilled.

260 Bus companies also found ways to cut costs in vehicle and fuel purchases. Out of all formal buses
 261 in the city, TDCC estimated that 38% had 7 to 10 years of operation, and 40% had 10 years or more. A
 262 large majority of these buses had been bought from Korean bus companies after they reached the Korean
 263 limit of 7 years of operation – the limit in Ulaanbaatar is 12 years. Further, TDCC also reported that often
 264 the MGUB purchased these buses from the Korean bus companies directly, and then sold them to bus
 265 companies in Ulaanbaatar offering cheap financing mechanisms. Bus companies also purchased fuel from
 266 the MGUB through similar cheap financing mechanisms. These financing schemes basically functioned
 267 as channels for the MGUB to subsidize bus companies, with the added feature that bus companies often

268 did not even pay back to the city their loans in full; instead, debts were commonly pardoned when ‘new’
 269 buses were purchased or bus fare negotiations arose.

270 These benefits came on top of the MNT 53 billion (US\$ 29 million) in annual transfers from the
 271 NGM to the bus companies, by way of TDCC, to repay for the subsidized travel of students, elderly, and
 272 people with disabilities. However, TDCC had no effective mechanism to know the exact number of
 273 subsidized passengers that rode on each route any given day, week or month. Instead, the total subsidy
 274 amount was calculated under the assumption that every person in Ulaanbaatar that qualified for
 275 subsidized travel made two public transport trips every day, and then that figure was distributed
 276 proportionally between bus companies according to the routes and services that they operated. TDCC
 277 paid out these subsidized travel compensations to bus companies once a month. While TDCC considered
 278 very probable that the subsidy allocations exceeded the proper compensation for actual rides carried out
 279 by the target populations, no corrective measures were in place. As such, these transfers acted as one
 280 additional source of government support for bus companies to meet their bottom line.

281

282 **THE ONGOING REFORM EFFORT**

283

284 **Impetus for the Reforms**

285 By 2014, two mass transit systems had been considered for Ulaanbaatar. The first was a metro line
 286 running from east to west along Peace Avenue. A prefeasibility analysis had been completed with support
 287 from the Japan International Cooperation Agency (JICA), but a feasibility analysis and detailed designs
 288 were required for the project to progress. JICA and the NGM had discussed a potential \$50 million loan
 289 to carry out these studies, but those discussions seemed to be stalled at the time. The second project was a
 290 BRT system. Since the metro would run along Peace Avenue, the first BRT lines would be north-south
 291 lines to establish a mass transit network. The BRT system had been developed in partnership with the
 292 Asian Development Bank (ADB), and more detailed feasibility studies had already been completed. On
 293 August 2012, the ADB board approved a \$59.9 million loan to complete the designs and build
 294 Ulaanbaatar’s the first BRT line; however, in August 2014, more than two years later, the Parliament had
 295 not yet granted approval to this loan, leaving the BRT project in limbo.

296 Both the metro and the BRT initiatives appeared to be stuck between the interests of the MGUB
 297 and the NGM. The MGUB supported both projects eagerly and wanted to move forward in their
 298 development as soon as possible, as public pressure to improve transport conditions in the city was
 299 mounting. The NGM, however, did not want to take on any additional debt at a time when the economy
 300 was slowing down and public resources were scarce again, and thus, it did not follow up on JICA’s metro
 301 efforts and put on hold the approval of the ADB loan for the BRT. The MGUB figured it needed to find a
 302 way to move forward without the support of the NGM, and found inspiration in some of the components
 303 and reforms suggested for the BRT.

304

305 **The Smart Bus Reforms**

306 The ADB recommended that the BRT implemented a suite of intelligent transport systems (ITS) to
 307 deliver a distinct higher quality service vis-à-vis the existing public transport services in Ulaanbaatar. The
 308 first element was an automated fare collection system to provide a fast cashless payment method for
 309 passengers, also able to store and communicate information to deliver additional benefits to passengers
 310 and provide valuable information to TDCC. The second element was a bus management system,
 311 combining computer-aided dispatching and automatic vehicle location systems (CAD/AVL) to enhance
 312 transport operations in real time, as well as improve broader planning and management of the bus fleet.
 313 Finally, the third element was a passenger information system, building on the AVL to provide real time
 314 information to passengers through message boards, websites, cellphone apps, etc., about buses’ arrival
 315 and departure times, as well as trip planning tools.

316 TDCC considered that those three ITS elements, which came to be referred to as the ‘Smart Bus’
 317 systems, could be applied to regular bus services in the city to deliver improvements in service quality,
 318 enhance companies’ financial management practices, and bring more clarity to the distribution of

319 government subsidies. TDCC believed that main challenge to the implementation of Smart Bus systems
 320 lied in their procurement and operational cost, since there were no public funds available from the NGM
 321 or the MGUB to pay for them. Accordingly, the MGUB and TDCC figured that their only alternative was
 322 to bid out to the private sector a concession for both the procurement and the operation of the Smart Bus
 323 systems. Unfortunately, the urgency to improve public transport services for citizens, perhaps invigorated
 324 by the potential political gains that such improvements could deliver, transpired in a rather hurried
 325 planning, structuring, and awarding of the concession.

326 The UB City and Data Card Consortium LLC (UBDCC), the winning bidder, was the only bidder
 327 for the concession. Korea Smart Card Co., a world leader in automated payment systems for transport
 328 services, controlled a majority stake in UBDCC; the MGUB held a minority stake in UBDCC. The
 329 concession contract was signed in September 2014, mandating that the suite of Smart Bus systems was
 330 fully implemented 240 days later. UBDCC's initial investment was estimated to be about \$13 million,
 331 which would be recovered by obtaining a 10% of the total fare collection during a period of 4 years and 8
 332 months after the systems' implementation, or until UBDCC recovered their investment. However, the
 333 concession contract seemed to lack detail in the scope of the activities and obligations that the delivery
 334 and operation of the Smart Bus systems entailed. TDCC appeared to trust that UBDCC, by way of the
 335 broad range of international expertise within Korea Smart Card Co., would be able to 'fill in the blanks'
 336 to interpret TDCC's vision for the Smart Bus systems.

337 In order to maximize the impact of implementing the Smart Bus systems, TDCC also decided to
 338 undertake a series of parallel reforms to Ulaanbaatar's bus system. The first reform was a major redesign
 339 of the city's bus route network, moving away from the former radial structure, to more of a hub and spoke
 340 structure with main lines running along high demand corridors, and complementary access routes feeding
 341 on to those. 60% of the old bus routes would change with the main objective of minimizing travel times
 342 for most users. The new route network also reduced route overlapping on Peace Avenue and other key
 343 corridors, while increasing bus service coverage out in the ger areas.

344 Another key reform was the creation of a new regulatory framework for bus operations. The
 345 inception of the automated fare collection system implied that a large portion of daily revenues would be
 346 cashless; instead, they would be amassed directly by UBDCC's clearing house. As such, the new
 347 regulation stipulated that cash revenues would also be collected on a daily basis by UBDCC – i.e. buses
 348 would still accept cash payments, but at the end of the day UBDCC representatives would collect all the
 349 cash revenue from the bus companies. In addition, the remuneration of bus companies would no longer be
 350 directly tied to demand. The new regulation stipulated that remunerations would be based on the total
 351 revenue generated by the bus system as whole and the total number of hours of public transport services
 352 provided: each bus company would be allocated a proportional amount of the daily revenues given the
 353 hours of service provided; and each company's 'hours of service' would be determined with the help of
 354 the new AVL equipment, with different effective 'time deductions' charged for violations to a series of
 355 performance measures related to the strict following of the routes, schedules and service plans assigned
 356 by TDCC to each company.

357

358 **Implementation and early outcomes**

359 TDCC decided that both the Smart Bus systems and the complementary reforms would be launched
 360 together. The Smart City systems were activated on July 29, 2015, marking the official start of the
 361 operational phase of the concession with UBDCC. The new route network and sector regulations were
 362 introduced on August 15, 2015. As such, in a period of two weeks, in a process that basically amounted to
 363 one 'big bang', the whole public transport system, as seen from both the perspective of the user and the
 364 perspective of the bus companies, had radically changed.

365 One of the first struggles with the new system was that the new hub and spoke route structure
 366 made people transfer routes more often than under the old radial structure. The operational coordination
 367 for transfers to be carried out efficiently had not yet been achieved, so people had to wait long stretches of
 368 time to get on their second or third buses. Moreover, since there was no special fare provision for
 369 transferring, people were forced to pay double or triple the amount that they were used to pay for a trip.

370 This is to say that under the new system, commute times became considerably longer and more expensive
 371 at the same once. Over time, citizens' frustrations grew louder and louder, as manifested in press articles
 372 and in the city's public complaint hotline. By November 2015, TDCC had already implemented a system
 373 whereby passengers using the new smart card received two free transfers within a 30-minute window of
 374 alighting their first bus. Smart card penetration, however, was only 40%, as opposed to 80% expected by
 375 TDCC after three full months of implementation. Also, still struggling with operational coordination
 376 issues, TDCC decided to bring back 40% of the old routes and modified many of the new ones to reduce
 377 transfers.

378 Bus companies also grew rapidly displeased with the new system. After a few months of
 379 operation, they began to argue that the new AVL/CAD was not properly documenting the hours of service
 380 provided, while piling on undeserved penalties – meaning, that they believed they were being
 381 remunerated less than what they deserved. They also claimed that subsidized passengers, such as students,
 382 the elderly, and people with disabilities, were not being properly accounted for, further affecting their
 383 eventual remuneration. Finally, it was now up to bus companies to compensate bus drivers and fare
 384 collectors, instead of the other way around. To cut costs, the majority of fare collectors were laid off with
 385 exception of few serving on the higher demand routes. Yet, even then bus companies claimed that they
 386 were incurring on important losses to abide by the service plans. When the idea that transfers would
 387 become free began to be discussed, bus companies' protests grew ever more vocal, and on October 7,
 388 2015 they went on strike. Following the negotiations, the MGUB agreed to pay out a monthly subsidy to
 389 every bus company to ensure that they could cover their operating costs – i.e. the MGUB would pay the
 390 difference between each company's monthly revenues, including subsidy allocations to it by the NGM for
 391 subsidized passengers, and the company's gross operating costs for the month.

392 By December 2015, it was evident that UBDCC was not fulfilling all of its duties under the
 393 concession agreement, or, at the very least, TDCC's expectations of how the Smart Bus systems were to
 394 complement the operational and regulatory reforms already implemented. UBDCC had been collecting
 395 10% of all public transport revenues in the city for months as service fee. And, surely, every single bus in
 396 the city had been equipped with an on-board unit that validated smart cards, generated GPS data for the
 397 AVL, and communicated directions from the control center to the driver. Yet, it was true also that the
 398 AVL/CAD was not facilitating operational coordination, and UBDCC had not staffed the control center
 399 with technical experts. It was also true that the AVL worked poorly in the peripheral areas of the city
 400 where cellphone coverage was weak and many trips seemed to go undocumented. Similarly, many
 401 features for the broader management of the bus system and to provide information to passengers had not
 402 been developed at all.

403 By December 2015, both users and bus companies had also learned how to game the system.
 404 Since fare collectors had been let go, the driver had become responsible for monitoring fare payments –
 405 i.e., verify that every passenger tapped in with a smart card or deposited the right amount of cash in the
 406 security box. Drivers, however, still needed to place their primary focus on the road, and many forms
 407 evasion grew rampant, including: (i) not paying at all (directly walking in); (ii) incomplete cash payments
 408 (quickly dropping an insufficient cash amount in the box); and (iii) the use of 'empty' smart cards
 409 intended for students, the elderly, and people with disabilities by regular adults. With regards to bus
 410 companies, TDCC and UBDCC began to grow suspicious that they were tampering with the cash boxes
 411 before turning in revenues at the end of the day. In addition, given that AVL information was not yet
 412 reliable, TDCC had to trust that bus companies were fulfilling the service plans even if the AVL did not
 413 report that was the case – that meant, paying out daily remunerations and the monthly subsidies to match
 414 all operating costs.

415 TDCC and the MGUB had 'played their hand' and found themselves in a very weak position to
 416 deliver the changes they had envisioned. On the one hand, they were locked in a concession agreement
 417 that did not offer mechanisms to pressure UBDCC to implement the full suite of Smart Bus systems.
 418 UBDCC was already collecting its portion of the revenues and was irresponsive to requests by TDCC to
 419 speed up the development of new tools or the improvement of the existing ones. Bus companies, on the
 420 other hand, remained frustrated by the reforms, as many of them believed that the reforms had ran

421 profitable businesses into the ground; either way, the MGUB had already committed to ensuring cost
 422 recovery for every company even though TDCC did not have the proper tools to supervise service
 423 delivery and quality.

424 Meanwhile, congestion, pollution, and road safety incidents kept increasing in Ulaanbaatar.
 425 Moving about the city, be it by public transport, car, or walking, had only become more inefficient.
 426 Elections loomed in horizon in July 2016, the outcome for those in power at the MGUB unclear.

427

428 CONCLUSIONS

429 It is commonly accepted that there tend to be less bureaucratic and procedural barriers to planning and
 430 implementing large transport infrastructure projects or significant regulatory reforms in cities in
 431 developing economies vis-à-vis cities in more advanced economies. As such, the less restrictive context
 432 of cities in developing economies offers an opportunity for dynamic city leaders to try to bring about
 433 change in short periods of time and hopefully reap the benefits of that change at the ensuing elections.
 434 The case of the Smart Bus reforms in Ulaanbaatar demonstrates that change, however, does not happen
 435 overnight, and that there are high risks associated with trying to deliver change hastily and without the
 436 support of a thorough planning process.

437 Consideration of the growing literature on integrated transport and land use planning would had
 438 suggested that running high quality and profitable (or, at the very least, cost efficient) public transport
 439 services in Ulaanbaatar was already a tough proposition prior to the reforms (9, 10). Some of the roots of
 440 the problems lied in the city's built forms, and the structure and condition of its road network. Another
 441 critical element was that cars had taken over most of the city's road space and there were very few special
 442 facilities for public transport vehicles; as a result, the growing levels of congestion made public transport
 443 service provision even less efficient. These elements were not going to change with the implementation of
 444 the reforms, and there was no consideration of how they stood in the way of the reforms delivering on
 445 their goals.

446 There was surely a high degree of wishful thinking behind the reforms, and little consideration of
 447 important lessons from reform efforts in other developing countries. For instance, in many cities in Latin
 448 America, traditional bus companies have mobilized their influences to postpone and derail public
 449 transport reforms and preserve the status quo (11). In Ulaanbaatar, the bus companies were used to seeing
 450 high profits on the basis of exploiting drivers and fare collectors, and the formal and *de facto* subsidies
 451 awarded to them. While the reforms aimed to align bus companies' economic incentives with the
 452 provision of better services, by December 2015 bus companies had already seized on the opportunities
 453 created by the lack of technical analysis and outreach conducted prior to reforms to gain new subsidies
 454 and an increase in the number of routes.

455 Similarly, in contexts of scarce economic resources and limited institutional capacity, the desire
 456 to outsource complex technical tasks to the private sector can be understood. However, most successful
 457 experiences in this field combined private sector investment and expertise with strong government
 458 guidance and supervision (11, 12). In Ulaanbaatar, the concession contract gave no effective oversight
 459 tools to TDCC or the MGUB over UBDCC. The selection of UBDCC, specifically, as the winning bidder
 460 also raised some questions. While Korea Smart Card Co had extensive expertise in automated fare
 461 collection systems, their experience designing and operating AVL/CAD systems was not as clear. It was
 462 not surprising then that in Ulaanbaatar the automated fare collection system was ready to go on the July
 463 29, 2015 launch date and it had functioned without hiccups ever since, while six months later the
 464 AVL/CAD and other complementary tools were not functioning well or simply had not been completed
 465 yet. Bundling fare collection, AVL/CAD, and passenger information systems in one single concession
 466 seemed like the wrong approach altogether, at a time when the industry was moving towards
 467 modularization of these different elements (13, 14).

468 Finally, the rollout of the reforms in one big bang disregarded many other cases around the world
 469 where big bus reforms were implemented in one big sweep and failed miserably because of it (15). The
 470 lesson learned was to implement these type of reforms gradually, perhaps piloting the changes in a few
 471 strategic areas, or on a few bus routes, to identify the problems and fix them, before moving on to

Velez, Chen, Bat Orig, Ardila-Gomez

472 citywide implementation. That type of gradual rollout could have helped TDCC and the MGUB avoid
473 many of the problems they were still facing six months after the launch date of the reforms.

474 Surely sound planning takes time and requires resources, while the priority for the MGUB
475 seemed to be to deliver ‘something’ promptly, cash the returns at the ballot box, and deal with the
476 consequences later – only this time around, the consequences seemed to had caught up to them much
477 earlier than planned.

478

479 REFERENCES

480

- 481 1. Ulaanbaatar City Statistics Office, “Table 1: Population” (2016). Retrieved from
482 <http://ubstat.mn/StatTable=11>. Last accessed July 2016.
- 483 2. World Bank, “Data: Mongolia: Annual GDP Growth” (2016). Retrieved from
484 <http://data.worldbank.org/country/mongolia>. Last accessed July 2016.
- 485 3. Capital City Master Planning Agency, *Ulaanbaatar 2020 Master Plan and Development Approaches*
486 *for 2030: Technical Summary*. Ulaanbaatar, 2014, pp. 24.
- 487 4. World Bank, *East Asia’s Changing Urban Landscape: Measuring a Decade of Spatial Growth*.
488 Urban Development Series. World Bank, Washington, DC, 2015, pp.104.
- 489 5. Capital City Master Planning Agency, *Ulaanbaatar 2020 Master Plan and Development Approaches*
490 *for 2030*. Ulaanbaatar, 2014.
- 491 6. Kamata, T., J. Reichert, T. Tsevegmid, Y. Kim and B. Sedgewick. *Managing Urban Expansion in*
492 *Mongolia, Best Practices in Scenario-Based Urban Planning*.
- 493 7. World Bank, “Urban Transport Analysis Tool (UT-DAT)”. Retrieved from
494 <http://www.worldbank.org/en/topic/transport/publication/urban-transport-data-analysis-tool-ut-dat1>.
495 Last accessed July 2016.
- 496 8. Transport Department of the Capital City, “The Current State of Urban Transportation Sector”.
497 Retrieved from <https://prezi.com/mwehm-7ilzka/transportation-department>. Last accessed July 2016.
- 498 9. R.Cervero, “Linking urban transport and land use in developing countries”, *Journal of Transportation*
499 *and Land Use*, Vol. 6 No. 1, 2013, pp. 7–24.
- 500 10. Hiroaki, S., R. Cervero, and K. Iuchi, *Transforming Cities with Transit: Transit and Land-Use*
501 *Integration for Sustainable Urban Development*. World Bank, Washington, DC, 2013.
- 502 11. A. Ardila, “How Public Transportation’s Past Is Haunting Its Future in Bogotá, Colombia”,
503 *Transportation Research Record: Journal of the Transportation Research Board*, No. 2038,
504 *Transportation Research Board of the National Academies*, Washington, D.C., 2007, pp. 9–15.
- 505 12. A. Estache and A. Gomez-Lobo, “Limits to Competition in Urban Bus Services in Developing
506 Countries”, *Transport Reviews*, Vol. 25, No. 2, pp. 139-158.
- 507 13. Transport for London, “iBus Contract Extension”, Support Paper for Board Consideration, February
508 4, 2015, Item 11. Retrieved from [http://content.tfl.gov.uk/board-20150204-part-1-item-11-ibus-](http://content.tfl.gov.uk/board-20150204-part-1-item-11-ibus-contract-ext.pdf)
509 [contract-ext.pdf](http://content.tfl.gov.uk/board-20150204-part-1-item-11-ibus-contract-ext.pdf). Last accessed July 2016.
- 510 14. Pulido, D. and D. Canales, “Real-Time Passenger Information: Getting It Right”, *Connections*, Note
511 No. 27, World Bank, November 2015. Retrieved from
512 [http://pubdocs.worldbank.org/en/750371447968212509/ConnectionsNote27-1607516-Web-](http://pubdocs.worldbank.org/en/750371447968212509/ConnectionsNote27-1607516-Web-00000002.pdf)
513 [00000002.pdf](http://pubdocs.worldbank.org/en/750371447968212509/ConnectionsNote27-1607516-Web-00000002.pdf). Last accessed July 2016.
- 514 15. A. Gomez-Lobo and J. Briones, “Incentive Structure in Transit Concession Contracts: The Case of
515 Santiago, Chile, and London, England”, *The Clean Air Institute*, Washington, DC, 2013. Retrieved at
516 [http://ppp.worldbank.org/public-private-partnership/library/incentive-structure-transit-concession-](http://ppp.worldbank.org/public-private-partnership/library/incentive-structure-transit-concession-contracts-case-santiago-chile-and-london-england)
517 [contracts-case-santiago-chile-and-london-england](http://ppp.worldbank.org/public-private-partnership/library/incentive-structure-transit-concession-contracts-case-santiago-chile-and-london-england). Last accessed July 2016.

518